

অধ্যক্ষৰ কাৰ্যালয়
Office of the Principal

পশ্চিম গুৱাহাটী মহাবিদ্যালয়
অমৃত ভড়ালী পথ, ধৰাপুৰ, গুৱাহাটী-৭৮১০১৭, অসম
PASCHIM GUWAHATI MAHAVIDYALAYA
Amrit Bharali Path, Dharapur, P.O : Azara,
Guwahati-781017, Kamrup, Assam



URL : <http://www.pgmddharapur.ac.in>
E-mail : pgm17dharapur@gmail.com
pgmahavidyalaya@rediffmail.com
Tel. : 0361-2845021/2845023/2845821 (Office)
Fax : 0361-2845021

From : Sri Rana Sarmah, M.Sc., Ph.D., Principal শ্ৰী ৰাণা শৰ্মা, এম. এছ.ডি., পি.এইছ.ডি., অধ্যক্ষ

No.....

Date.....

No.PGM/Quotation/87/1023

Date.25.09.2021

SHORT TENDER NOTICE

Sealed tenders are invited from the contractor under Govt. Dept. only for the following works, which will be received by the undersigned up to 12 noon of 05-10-2021 and will be opened at 1 p.m. on the same day. In case the office happens to be closed on the date of receiving/opening of tenders, the tender will be received/opened on the next working day as per the same schedule of time. The tender documents will be issued from the Principal, Paschim Guwahati Mahavidyalaya, Dharapur, Guwahati 17 against the non-refundable payment of requisite cost (non-refundable) in terms of Bank Demand Draft/Bankers Cheque/Pay Orders only pledged in favour of the undersigned and payable at Guwahati. The contactors must submit i) Copy of ID Proof ii) Copy of residential Proof iii) Copy of Labour Licence iv) copy of trade licence, v) Copy of GST Registration certificate vi) Copy of Last IT payment receipt vii) Copy of bank details page of Bank Pass Book along with their tenders. The bidder is also required to make payment of requisite Earnest Money (2% of estimated amount for general category i.e. Rs.6500/- (Rupees six thousand five hundred) only and 1% for SC/ST/OBC/MOBC i.e. Rs.3300/- (Rupees three thousand three hundred) in terms of TDR/CDR/FDR only pledged in favour of undersigned without which the tender shall be rejected directly. The rate of the items should be quoted both in figures and words clearly. Details of tender and specifications of work may be seen in the college office during all working hours up to 09.10.2021.

Sl.No.	Name of works	Estimated amount Rs.	Time for completion	Cost of tender documents Rs.
1.	Name of work: Construction of one ramp and corridor and repairing of verandah at college campus of Paschim Guwahati Mahavidyalaya, Dharapur, Guwahati-17 Works included : 1. Repairing of old building ground floor veranda and laying tiles 2. Construction of one ramp near Principal's Chamber and laying tiles 3. Construction of corridor between office building and Women's Hostel and without tiles	3.41 Lakhs	On or before 19.10.2021 (In no cases(s) this date will be extended)	500.00

Documents (self-attested) to be attached

1. Copy of ID Proof
2. Copy of Residential Proof
3. Copy of Labour/Trade License
4. Copy of GST Registration certificate
5. Copy of Last IT payment receipt
6. Copy of bank details page of Bank Pass Book
7. Cast Certificate, if any

Dona
Principal 25.9.2021
Paschim Guwahati Mahavidyalaya
Principal
Paschim Guwahati Mahavidyalaya
P.O. Dharapur, Guwahati-17

Copy to :

1. The Chairman, G.B. of Paschim Guwahati Mahavidyalaya
2. Consultant Engineer, Paschim Guwahati Mahavidyalaya
4. College Notice Board & website

TENDER PAPER

Tender Notice No. Date.....

Name of Work: Construction of one ramp and corridor and repairing of verandah at college campus of Paschim Guwahati Mahavidyalaya, Dharapur, Guwahati-17

- Works included :**
1. Repairing of old building ground floor veranda and laying tiles
-
2. Construction of one ramp near Principal's Chamber
-
3. Construction of corridor between office building and Women's Hostel

S/N	DSR 2020-21	Description	Qty	Unit	Rate	Amount (Rs.)
A		Repairing of Old Building Ground Floor Verandah	---	---	---	---
1	11.39	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm or more (thickness to be specified by the manufacturer), of 1 st quality conforming to IS : 15622, of approved make, in colours White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement: 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete	224. 190	Sqm		
B		Construction of Ramp near Principal's Chamber and Construction of Corridor from Office Building to Women's Hostel	---	---	---	---
	2.1	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including getting out and disposal of excavated earth up-to 50 m and lift upto 1.5 m, as directed by Engineer-in- Charge:	---	---	---	---
	2.1.1	All kinds of soil	31.865	Sqm		
2	2.25	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50m and lift upto 1.5m	5.24 3	cum		
3	16.79	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge	3.18 7	cum		

Signature of the Authorised person of Farm/Contractor with seal


Sanjay Kumar
Principal
Paschim Guwahati Mahavidyalaya
P.O. Dharapur, Guwahati-17

4	2.27	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete	0.90 2	cum		
5	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :	---	---	---	---
	4.1.5	1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources)	3.71 3	cum		
6	6.1	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand)	1.60 00	cum		
7	16.42	Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete	0.52 3	cum		
8	11.2	Chequered precast cement concrete tiles 22 mm thick in footpath & courtyard, jointed with neat cement slurry mixed with pigment to match the shade of tiles, including rubbing and cleaning etc. complete, on 20 mm thick bed of cement mortar 1:4 (1 cement : 4 coarse sand) Medium shade pigment using 50% white cement 50% Grey cement	18.0 40	sqm		
9	11.39	In steps Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in colours White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement: 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete	5.44 0	sqm		
10	13.2	Cement Plaster, sides of ramp and steps 15mm cement plaster on rough side of single or half brick wall of mix 1:4 (1 cement : 4 fine sand)	5.67 0	sqm		
Total tendered amount Rs.						

Signature of the Authorised person of Farm/Contractor with seal

Full name of the Contractor/Farm person.....

Full Address of the Contractor/Farm.....


Principal

Paschim Guwahati Mahavidyalaya
P.O. Dherapar, Guwahati-17